



1 FLOOR PLAN - FIRST FLOOR  
1" = 10'-0"

WALL LOAD SCHEDULE												
MARK	ELEV.	DEAD LOAD Klb/ft	LIVE LOAD Klb/ft	SNOW LOAD Klb/ft	W-E WIND LOAD			N-S WIND LOAD			EARTH PRES. IN PLANE Klb/ft	CHORD LOAD DEAD IN PLANE Klb
					UP/RT Klb/ft	DOWN/RT Klb/ft	IN PLANE Klb/ft	UP/RT Klb/ft	DOWN/RT Klb/ft	IN PLANE Klb/ft		
WL1	-0'-4"	1.51	3.35	2.01	0.40	N/A	N/A	0.40	N/A	0.15	N/A	N/A
WL2	-0'-4"	0.83	0.74	0.44	0.40	N/A	N/A	0.40	N/A	0.15	N/A	N/A
WL3	-0'-4"	1.12	1.84	1.10	0.40	N/A	N/A	0.40	N/A	0.15	N/A	N/A
WL4	-0'-4"	1.05	1.57	0.94	0.40	N/A	N/A	0.40	N/A	0.15	N/A	N/A
WL5	-0'-4"	0.72	0.33	0.20	0.40	N/A	0.39	0.40	N/A	N/A	N/A	N/A
WL6	-0'-4"	1.11	1.79	1.07	0.40	N/A	N/A	0.39	0.40	N/A	N/A	N/A
WL7	-0'-4"	1.58	1.67	1.00	1.61	2.39	N/A	N/A	N/A	0.15	N/A	N/A
WL8	-0'-4"	0.50	N/A	N/A	0.39	N/A	1.20	N/A	N/A	N/A	N/A	N/A
WL9	-0'-4"	1.73	2.26	1.36	1.86	N/A	N/A	0.15	N/A	N/A	N/A	N/A
WL10	-0'-4"	1.52	1.46	0.88	N/A	N/A	0.39	1.28	N/A	N/A	2.30	N/A
WL11	-0'-4"	0.50	N/A	N/A	N/A	N/A	0.39	1.28	N/A	N/A	2.30	N/A
WL12	-0'-4"	1.55	1.57	0.94	N/A	1.08	N/A	N/A	N/A	0.15	2.30	N/A
WL13	-0'-4"	1.58	1.67	1.00	N/A	1.08	N/A	N/A	N/A	0.15	2.30	N/A
WL14	-0'-4"	0.27	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
WL15	-0'-4"	1.92	1.33	0.44	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
WL16	11'-2"	0.95	1.10	1.10	0.40	N/A	N/A	0.40	N/A	0.16	N/A	N/A
WL17	11'-2"	0.94	1.07	1.07	0.40	N/A	0.39	0.40	N/A	N/A	N/A	N/A
WL18	11'-2"	0.69	0.20	0.20	0.40	N/A	0.39	0.40	N/A	N/A	N/A	N/A
WL19	-1'-8"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	2.30	N/A
WL20	-1'-8"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	2.30	N/A
WL21	-0'-4"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1.94	1.76

POINT LOAD SCHEDULE			
MARK	DEAD LOAD Klb	LIVE LOAD Klb	SNOW LOAD Klb
PL1	15.24	25.01	15.01
PL2	30.47	50.02	30.02
PL3	15.24	25.01	15.01
PL4	17.84	17.40	10.50

SUPERIMPOSED UNIFORM LOAD SCHEDULE			
MARK	DEAD LOAD PSF	LIVE LOAD PSF	SNOW LOAD PSF
	150.00	150.00	42.00
	20.00	100.00	N/A
	20.00	100.00	N/A
	20.00	100.00	N/A
	20.00	40.00	N/A



## LOADING PLAN

Date	Description
06.21.2019	Loading
06.29.2019	in plane lateral loads
07.04.2019	increase in courtyard load values

**CAPITAL GROUP**  
Developer: W Capital Group  
tyler@wcapitalgroup.com | 608.345.9848

**Architect: OpeningDesign**  
316 W Washington Ave | Suite 675  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

**ROYAL CONSTRUCTION**  
General Contractor: ROYAL CONSTRUCTION  
3653 Greenway Street | Eau Claire, WI 54701  
jim@royalbuild.com | 715.225.6377

**Cedar Corporation**  
Civil Engineer: CEDAR CORPORATION  
604 Wilson Avenue | Menomonie, WI 54751  
kevin.olum@cedarcorp.com | 715.235.9081

**Structural Engineer: Structural Engineering**  
Calle Apolonia Morales, 628036 Madrid,  
Lperetola@xcelengineering.xyz | +34 610 56 26 37

**Ennovation Engineering Services Incorporated**  
Structural Engineer: Structural Engineering  
4729 Dale-Curtain Dr, McFarland, WI 53558  
kthey@ennovationbuild.com

**Hovland's Heating, Ventilation & Conditioning**  
Mechanical Engineer: HOVLAND'S HVAC  
10954 E. Mabey Street | Chippewa Falls, WI 54729  
jhansen@hovlands-inc.com | 715.552.5595

**Electrical Engineer: PRISM DESIGN ELECTRICAL CONSULTANTS INC**  
E8403 State Rd 85 | Mondovi, WI 54755  
bhaigen@prismdesign-electrical.com | 715.797.0602

**TAILORED ENGINEERING**  
Plumbing Engineer: TAILORED ENGINEERING  
1600 Aspen Commons | Ste 210 | Middleton, WI 53562  
bnovak@tailoredeng.com | 608.209.7500