



SUPERIMPOSED UNIFORM LOAD SCHEDULE				
MARK	DEAD LOAD PSF	LIVE LOAD PSF	SNOW LOAD PSF	COMMENTS
	110.00	100.00	42.00	YARDS AND TERRACES PEDESTRIAN
	20.00	100.00	N/A	CORRIDORS FIRST FLOOR
	20.00	100.00	N/A	STAIRS AND EXITS
	20.00	100.00	N/A	STORE FIRST FLOOR
	20.00	40.00	N/A	PRIVATE ROOMS MULTIFAMILY DWELLING

POINT LOAD SCHEDULE

Mark Dead Load | Live Load | Snow Load | Wind Load

Klb Klb Klb Klb

PL2 34.73 53.36 23.46 -14.82

PL3 10.42 16.01 7.04 -4.45
PL4 11.63 17.74 7.77 -4.91
PL5 11.44 14.00 9.19 3.91

PL1 31.14 42.86 22.35



Architect: OpeningDesign 316 W Washington Ave | Suite 675 Madison, WI 53703 ryan@openingdesign.com | 773.425.6456

General Contractor: ROYAL CONSTRUCTION 3653 Greenway Street | Eau Claire, WI 54701

jim@royalbuilt.com | 715-225-6377







I.pereztato@xcengineering.xyz | +34 610 56 26 37

Structural Engineer: Structural Engineering 4729 Dale-Curtain Dr, McFarland, WI 53558 kfrey@ennovationbuilt.com



jhansen@hovlands-inc.com | 715.552.5595 Electrical Engineer: PRISM DESIGN ELECTRICAL

CONSULTANS INC

E8403 State Rd 85 | Mondovi, WI 54755

bhalgren@prismdesign-electrical.com | 715.797.0602



N/A N/A N/A

Plumbing Engineer: TAILORED ENGINEERING 1600 Aspen Commons | Ste 210 | Middleton, WI bnovak@tailoredeng.com | 608.209.7500

Date Description 06.21.2019 Loading 06.29.2019 in plane lateral load 07.04.2019 increase in courtyar load values 10.10.2019 update load values