WOOD SHEAR WALL SCHEDULE													
			n plate nment lation)										
Shear wall	Sheathing material	Panel thickness	Blocking	Minimum fastener penetration in framing member or blocking	Fastener type and size	Panel edge fastener spacing	Nominal unit shear capacity $v_{_{w}}$	Hold-down anchor capacity	Hold down studs	Hold down anchor type	Number of bolts (1 in diameter, 4 inch embedment depth)	Bolt spacing	Bottom plate attachment (floor to floor)
ID		(in)		(in)		(in)	(plf)	(kip)				(in)	
SW_N3A	Wood structural panels – sheathing	3/8	YES	1-3/8	8d	4	840	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 25 in. o/c; 30 fasteners in 2 rows.
SW_N3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 24 in. o/c; 16 fasteners in 1 row.
SW_N3C	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 21 in. o/c; 35 fasteners in 2 rows.
SW_N3D	Wood structural panels – sheathing	3/8	YES	1-3/8	8d	4	840	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 25 in. o/c; 30 fasteners in 2 rows.
SW_N2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 14 in. o/c; 52 fasteners in 2 rows.
SW_N2B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-		-	-	16d (d= 0.268 in) nails at 13 in. o/c; 28 fasteners in 1 row.

SW_N2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-	Simpson HDU4-SDS2.5	-	-	16d (d= 0.268 in) nails at 12 in. o/c; 59 fasteners in 2 rows.
SW_N2D	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 14 in. o/c; 52 fasteners in 2 rows.
SW_N1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	3	(1)	Simpson HDU11-SDS2.5	10	36	SDWS log screw (d= 0.197 in) at 12 in. o/c; 58 fasteners in 2 rows.
SW_N1B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-		11	36	16d (d= 0.268 in) nails at 19 in. o/c; 39 fasteners in 2 rows.
SW_N1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-	Simpson HDU4-SDS2.5	11	36	wood screws 20 (d= 0.32 in) at 19 in. o/c; 40 fasteners in 2 rows.
SW_N1D	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	3	(1)	Simpson HDU11-SDS2.5	10	36	SDWS log screw (d= 0.197 in) at 12 in. o/c; 60 fasteners in 2 rows.
SW_S3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_S3B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_S2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	4	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 13 in. o/c; 54 fasteners in 2 rows.
SW_S2B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	4	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 13 in. o/c; 54 fasteners in 2 rows.
SW_S1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	7	(3)	Simpson HD19	10	36	SDWS log screw (d= 0.197 in) at 8 in. o/c; 76 fasteners in 2 rows.
SW_S1B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	7	(3)	Simpson HD19	10	36	SDWS log screw (d= 0.197 in) at 8 in. o/c; 76 fasteners in 2 rows.

SW_E3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	3	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 16 in. o/c; 46 fasteners in 2 rows.
SW_E3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 12 in. o/c; 30 fasteners in 1 row.
SW_E3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	6	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 15 in. o/c; 32 fasteners in 2 rows.
SW_E2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	5	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 11 in. o/c; 64 fasteners in 2 rows.
SW_E2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-	Simpson HDU4-SDS2.5	-	-	16d (d= 0.268 in) nails at 14 in. o/c; 51 fasteners in 2 rows.
SW_E2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	10	(4)	Simpson HD19	-	-	SDWS log screw (d= 0.197 in) at 9 in. o/c; 54 fasteners in 2 rows.
SW_E1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	13	(4)	Simpson HD19	7	36	SDWS log screw (d= 0.197 in) at 7 in. o/c; 64 fasteners in 2 rows.
SW_E1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_E1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	6	(2)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 10 in. o/c; 72 fasteners in 2 rows.
SW_W3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	3	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 16 in. o/c; 46 fasteners in 2 rows.
SW_W3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 12 in. o/c; 30 fasteners in 1 row.
SW_W3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	6	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 15 in. o/c; 32 fasteners in 2 rows.
SW_W2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	5	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 11 in. o/c; 64 fasteners in 2 rows.

SW_W2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-	Simpson HDU4-SDS2.5	-	-	16d (d= 0.268 in) nails at 14 in. o/c; 51 fasteners in 2 rows.
SW_W2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	10	(4)	Simpson HD19	-	-	SDWS log screw (d= 0.197 in) at 9 in. o/c; 54 fasteners in 2 rows.
SW_W1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	9	(3)	Simpson HD19	9	30	SDWS log screw (d= 0.197 in) at 7 in. o/c; 64 fasteners in 2 rows.
SW_W1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_W1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	6	(2)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 10 in. o/c; 72 fasteners in 2 rows.
SW_EC3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-		-	-	16d (d= 0.268 in) nails at 18 in. o/c; 42 fasteners in 2 rows.
SW_EC3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 60 in. o/c; 7 fasteners in 1 row.
SW_EC3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 19 in. o/c; 40 fasteners in 2 rows.
SW_EC2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	-	-	Simpson HDU4-SDS2.5	-	1	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_EC2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_EC2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	-	-	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 12 in. o/c; 58 fasteners in 2 rows.