

CMU WALL REINFORCING SCHEDULE				
MARK	WALL THICKNESS	VERTICAL REINFORCEMENT & SPACING	REINFORCEMENT LOCATION IN CELL	MIN. FIRE RATING
MW.1	8"	#5 AT 48" O/C MAX	CENTER	2HR
MW.2	8"	#6 AT 16" O/C MAX	INSIDE FACE	2HR
MW.3	6"	#5 AT 48" O/C MAX	CENTER	2HR
MW.4	10"	#5 AT 48" O/C MAX	CENTER	2HR

• PROVIDE CMU WALL REINFORCING ABOVE AND BELOW ALL MANSORY OPENINGS. EXTEND THE LENGTH OF THE REBARS BY 23" OR 40 BAR DIAMETERS PAST THE EDGE OF THE OPENING.
• DOWELS INTO FOOTING TO MATCH VERTICAL REINFORCEMENT SPACING AND LOCATION
• REFER TO REBAR CONTINUITY FOR MIN. LAP DISTANCES OF REBAR
• ALL FIREWALL CONSTRUCTION TO USE LIMESTONE CMU
• HORIZONTAL JOINT REINFORCING (W1.7) AT 16" O.C. VERTICALLY (8" O.C. AT PARAPET WALL LOCATIONS)
• HORIZONTAL JOINT REINFORCING TO BE HDG AT EXTERIOR WALLS, AND MILD GALVANIZED FOR INTERIOR WALLS
• 2HR RATING: 4" 2 CORE 75% SOLID, 8" 2 CORE 58% SOLID, 10" CMU: 2 CORE REGULAR

MASONRY WALL FOOTING SCHEDULE			
MARK	WIDTH	THICKNESS	LONGITUDINAL
MWF.1	2'-0"	1'-0"	(2)#5
MWF.2	3'-0"	1'-2"	(3)#5

• REFER TO STRUCTURAL NOTES SHEET FOR LAPS IN STEEL REINFORCEMENT.
• REFER TO FOUNDATION PLAN FOR TOP OF FOOTING ELEVATIONS.
• ALL FOOTING EXCAVATIONS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE

THICKENED SLAB SCHEDULE				
MARK	DIMENSIONS	REINFORCEMENT	REMARKS	
	WIDTH (xCONT)	THICKNESS	LONGITUDINAL	
TS20	2'-0"	1'-0"	(2) #5	

• REFER TO REBAR CONTINUITY FOR MIN. LAP DISTANCES OF REBAR
• SEE FOUNDATION PLANS FOR TOP OF FOOTING ELEVATIONS
• THE PROJECTS GEOTECHNICAL ENGINEER SHOULD INSPECT/APPROVE ALL FOOT EXCAVATIONS BEFORE POURING CONCRETE

WALL FOOTING SCHEDULE				
MARK	DIMENSIONS	REINFORCEMENT	REMARKS	
	WIDTH	THICKNESS	LONGITUDINAL	TRANSVERSE
WF26	2'-6"	1'-2"	(3)-#5	
WF30	3'-0"	1'-2"	(3)-#5	
WF42	3'-6"	1'-2"	SEE DETAIL 2/S202	SEE DETAIL 2/S202
WF48	4'-6"	1'-2"	(5)-#5	

• SEE FOUNDATION PLANS FOR TOP OF FOOTING ELEVATIONS
• THE PROJECTS GEOTECHNICAL ENGINEER SHOULD INSPECT/APPROVE ALL FOOT EXCAVATIONS BEFORE POURING CONCRETE
• UNO ALL REINFORCING LAPS TO BE CLASS B LAP SPICES

COLUMN FOOTING SCHEDULE										
Type Mark	Type	No.	El. @ Top	Width	Length	Depth	Volume	Bottom Reinforcing	Long	Short
FT70	FT70 - 7'-0x7'-0x1'-8	1	-14'-0"	7'-0"	7'-0"	1'-8"	81.67 CF	(10)-#7	(10)-#7	
FT90	FT90 - 9'-0x9'-0x2'-1	7	-14'-0"	9'-0"	9'-0"	2'-1"	168.75 CF	(10)-#8	(10)-#8	
FT96a	FT96a - 9'-6x9'-6x2'-6	1	-14'-0"	9'-6"	9'-6"	2'-6"	225.63 CF	(10)-#7	(10)-#7	
FT100a	FT100a - 10'-0x10'-0x2'-1	2	-14'-0"	10'-0"	10'-0"	2'-1"	208.33 CF	(11)-#8	(11)-#8	
FT100b	FT100b - 10'-0x10'-0x2'-3	3	-14'-0"	10'-0"	10'-0"	2'-3"	225.00 CF	(11)-#8	(11)-#8	
FT106	FT106 - 10'-6x10'-6x2'-4	1	-14'-0"	10'-6"	10'-6"	2'-4"	275.63 CF	(11)-#8	(11)-#8	
FT110a	FT110a - 11'-0x11'-0x2'-3	2	-14'-0"	11'-0"	11'-0"	2'-3"	272.25 CF	(12)-#8	(12)-#8	
FT110b	FT110b - 11'-0x11'-0x2'-6	2	-14'-0"	11'-0"	11'-0"	2'-6"	302.50 CF	(12)-#8	(12)-#8	
FT116	FT116 - 11'-6x11'-6x2'-6	1	-14'-0"	11'-6"	11'-6"	2'-6"	330.63 CF	(12)-#8	(12)-#8	
FT120a	FT120a - 12'-0x12'-0x3'-0	4	-14'-0"	12'-0"	12'-0"	3'-0"	432.00 CF	(13)-#8	(13)-#8	
FT120b	FT120b - 12'-0x12'-0x3'-6	3	-14'-0"	12'-0"	12'-0"	3'-6"	504.00 CF	(13)-#8	(13)-#8	
FT126	FT126 - 12'-6x12'-6x3'-6	1	-14'-0"	12'-6"	12'-6"	3'-6"	546.88 CF	(13)-#8	(13)-#8	

• REFER TO REBAR CONTINUITY FOR MIN. LAP DISTANCES OF REBAR
• SEE FOUNDATION PLANS FOR TOP OF FOOTING ELEVATIONS
• THE PROJECTS GEOTECHNICAL ENGINEER SHOULD INSPECT/APPROVE ALL FOOT EXCAVATIONS BEFORE POURING CONCRETE

CONCRETE WALL REINFORCING SCHEDULE						
MARK	TYPE	THICKNESS	REINFORCEMENT	MIN. FIRE RATING	REMARKS	
			VERTICAL	HORIZONTAL		
W1	CONCRETE	14"	5#'s AT 18" O.C.	5#'s AT 12" O.C.	2HR	inside face
W2	CONCRETE	10"	5#'s AT 12" O.C.	5#'s AT 12" O.C.	2HR	inside face
W3	CONCRETE	12"	4#'s AT 8" O.C.	4#'s AT 8" O.C.	2HR	both sides
W4	CONCRETE	8"	4#'s AT 12" O.C.	3#'s AT 12" O.C.	2HR	centered in wall thickness
W5	CONCRETE	8"	4#'s AT 12" O.C.	3#'s AT 12" O.C.	2HR	inside face
W6	CONCRETE	8"	4#'s AT 8" O.C.	4#'s AT 8" O.C.	2HR	both sides

• REFER TO REBAR CONTINUITY FOR MIN. LAP DISTANCES OF REBAR
• COORDINATE AND VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS AND EXISTIT CONDITIONS

CAPITAL GROUP
Developer: W Capital Group
tyler@wcapitalgroup.com | 608.345.9848

Architect: OpeningDesign
316 W Washington Ave | Suite 675
Madison, WI 53703
ryan@openingdesign.com | 773.425.6456

ROYAL CONSTRUCTION
General Contractor: ROYAL CONSTRUCTION
3653 Greenway Street | Eau Claire, WI 54701
jim@royalbuild.com | 715.225.6377

Cedar Corporation
Civil Engineer: CEDAR CORPORATION
604 Wilson Avenue | Menomonee, WI 54751
kevin.olum@cedarcorp.com | 715.235.9081


XC Structural Engineering
Structural Engineer: XC Structural Engineering
Calle Apolonia Morales, 628036 Madrid,
l.perezat@xcengineering.xyz | +34 610 56 26 37

Innovation Engineering Services Incorporated
Structural Engineer of Record: Innovation
4729 Dale-Curtain Dr, McFarland, WI 53558
kfrey@innovationbuild.com

Hovland's Mechanical Engineering
Mechanical Engineer: HOVLAND'S HVAC
10954 E. Welby Street | Chippewa Falls, WI 54729
jhansen@hovlands-inc.com | 715.552.5595

PRISM DESIGN ELECTRICAL CORPORATION INC.
Electrical Engineer: PRISM DESIGN ELECTRICAL CONSULTANTS INC
E8403 State Rd 85 | Mondovi, WI 54755
bhaigren@prismdesign-electrical.com | 715.797.0602

TAILORED ENGINEERING
Plumbing Engineer: TAILORED ENGINEERING
1600 Aspen Commons | Ste 210 | Middleton, WI 53562
brnovak@tailoredeng.com | 608.209.7500



Date	Description
07.08.2019	Footing/Foundation Permit
08.15.2019	75% CD Set
08.21.2019	Permit
10.09.2019	IFC - Foundation
10.15.2019	Updated Foundation Details
11.07.2019	Updated Foundation
03.27.2020	Updates
05.15.2020	Permit Revision #4
07.02.2020	Permit Revision #5
07.15.2020	Permit Revision #6
07.23.2020	Permit Revision #7

CANNERY TRAIL RESIDENCES - 1750 N OXFORD AVE. - EAU CLAIRE, WI