				V	VOC	D S	HEA	R W	ALL	SCHEDULE			
		Bottom plate attachment (foundation)											
Shear wall	Sheathing material	Panel thickness	Blocking	Minimum fastener penetration in framing member or blocking	Fastener type and size	Panel edge fastener spacing	Nominal unit shear capacity v _w	Hold-down anchor capacity	Hold down studs	Hold down anchor type	Number of bolts (1 in diameter, 4 inch embedment depth)	Bolt spacing	Bottom plate attachment (floor to floor)
ID		(in)		(in)		(in)	(plf)	(kip)				(in)	
SW_N3A	Wood structural panels – sheathing	3/8	YES	1-3/8	8d	4	840	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 25 in. o/c; 30 fasteners in 2 rows.
SW_N3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 24 in. o/c; 16 fasteners in 1 row.
SW_N3C	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	ı		-	ı	16d (d= 0.268 in) nails at 21 in. o/c; 35 fasteners in 2 rows.
SW_N3D	Wood structural panels – sheathing	3/8	YES	1-3/8	8d	4	840	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 25 in. o/c; 30 fasteners in 2 rows.
SW_N2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	4	(2)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 14 in. o/c; 52 fasteners in 2 rows.
SW_N2B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	-		-	-	16d (d= 0.268 in) nails at 13 in. o/c; 28 fasteners in 1 row.

SW_N2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	1	(1)	Simpson HDU4-SDS2.5	-	-	16d (d= 0.268 in) nails at 12 in. o/c; 59 fasteners in 2 rows.
SW_N2D	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	4	(2)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 14 in. o/c; 52 fasteners in 2 rows.
SW_N1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	7	(3)	Simpson HDU11-SDS2.5	10	36	SDWS log screw (d= 0.197 in) at 12 in. o/c; 58 fasteners in 2 rows.
SW_N1B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	-	ı		11	36	16d (d= 0.268 in) nails at 19 in. o/c; 39 fasteners in 2 rows.
SW_N1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	3	(1)	Simpson HDU4-SDS2.5	11	36	wood screws 20 (d= 0.32 in) at 19 in. o/c; 40 fasteners in 2 rows.
SW_N1D	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	7	(3)	Simpson HDU11-SDS2.5	10	36	SDWS log screw (d= 0.197 in) at 12 in. o/c; 60 fasteners in 2 rows.
SW_S3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_S3B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_S2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	თ	1860	6	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 13 in. o/c; 54 fasteners in 2 rows.
SW_S2B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	6	(2)	Simpson HDU11-SDS2.5	,	-	SDWS log screw (d= 0.197 in) at 13 in. o/c; 54 fasteners in 2 rows.
SW_S1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	10	36	SDWS log screw (d= 0.197 in) at 8 in. o/c; 76 fasteners in 2 rows.
SW_S1B	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	10	36	SDWS log screw (d= 0.197 in) at 8 in. o/c; 76 fasteners in 2 rows.
SW_E3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	3	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 16 in. o/c; 46 fasteners in 2 rows.

SW E3B	Wood structural	3/8	NO	1-3/8	8d	6	560		_		_		16d (d= 0.268 in) nails at 12
SW_LSB	panels – sheathing	3/0	110	1-3/0	- ou		500						in. o/c; 30 fasteners in 1 row.
SW_E3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	6	(2)	Simpson HDU11-SDS2.5	-	ı	SDWS log screw (d= 0.197 in) at 15 in. o/c; 32 fasteners in 2 rows.
SW_E2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	7	(3)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 11 in. o/c; 64 fasteners in 2 rows.
SW_E2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	1	(1)	Simpson HDU4-SDS2.5	-	1	16d (d= 0.268 in) nails at 14 in. o/c; 51 fasteners in 2 rows.
SW_E2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	-	1	SDWS log screw (d= 0.197 in) at 9 in. o/c; 54 fasteners in 2 rows.
SW_E1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	13	(4)	Simpson HD19	7	36	SDWS log screw (d= 0.197 in) at 7 in. o/c; 64 fasteners in 2 rows.
SW_E1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_E1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	9	(3)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 10 in. o/c; 72 fasteners in 2 rows.
SW_W3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	З	(1)	Simpson HDU4-SDS2.5	-	ı	wood screws 20 (d= 0.32 in) at 16 in. o/c; 46 fasteners in 2 rows.
SW_W3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 12 in. o/c; 30 fasteners in 1 row.
SW_W3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	4	1430	6	(2)	Simpson HDU11-SDS2.5	-	1	SDWS log screw (d= 0.197 in) at 15 in. o/c; 32 fasteners in 2 rows.

SW_W2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	7	(3)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 11 in. o/c; 64 fasteners in 2 rows.
SW_W2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	1	(1)	Simpson HDU4-SDS2.5	-	-	16d (d= 0.268 in) nails at 14 in. o/c; 51 fasteners in 2 rows.
SW_W2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	-	-	SDWS log screw (d= 0.197 in) at 9 in. o/c; 54 fasteners in 2 rows.
SW_W1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	13	(4)	Simpson HD19	9	30	SDWS log screw (d= 0.197 in) at 7 in. o/c; 64 fasteners in 2 rows.
SW_W1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_W1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	9	(3)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 10 in. o/c; 72 fasteners in 2 rows.
SW_EC3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	0	-		-	-	16d (d= 0.268 in) nails at 18 in. o/c; 42 fasteners in 2 rows.
SW_EC3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 60 in. o/c; 7 fasteners in 1 row.
SW_EC3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	3	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 19 in. o/c; 40 fasteners in 2 rows.
SW_EC2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_EC2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_EC2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	6	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 12 in. o/c; 58 fasteners in 2 rows.

SW_EC1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	6	36	SDWS log screw (d= 0.197 in) at 9 in. o/c; 42 fasteners in 2 rows.
SW_EC1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 22 in. o/c; 17 fasteners in 1 row.
SW_EC1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 9 in. o/c; 82 fasteners in 2 rows.
SW_WC3A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	0	-		-	-	16d (d= 0.268 in) nails at 18 in. o/c; 42 fasteners in 2 rows.
SW_WC3B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	0	560	-	-		-	-	16d (d= 0.268 in) nails at 60 in. o/c; 7 fasteners in 1 row.
SW_WC3C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	6	950	3	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 19 in. o/c; 40 fasteners in 2 rows.
SW_WC2A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	2	(1)	Simpson HDU4-SDS2.5	-	-	wood screws 20 (d= 0.32 in) at 21 in. o/c; 36 fasteners in 2 rows.
SW_WC2B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		-	-	16d (d= 0.268 in) nails at 32 in. o/c; 12 fasteners in 1 row.
SW_WC2C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	3	1860	6	(2)	Simpson HDU11-SDS2.5	-	-	SDWS log screw (d= 0.197 in) at 12 in. o/c; 58 fasteners in 2 rows.
SW_WC1A	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	6	36	SDWS log screw (d= 0.197 in) at 9 in. o/c; 42 fasteners in 2 rows.
SW_WC1B	Wood structural panels – sheathing	3/8	NO	1-3/8	8d	6	560	-	-		11	36	16d (d= 0.268 in) nails at 22 in. o/c; 17 fasteners in 1 row.
SW_WC1C	Wood structural panels – sheathing	19/32	YES	1-1/2	10d	2	2435	11	(4)	Simpson HD19	11	36	SDWS log screw (d= 0.197 in) at 9 in. o/c; 82 fasteners in 2 rows.