## schedule

1st FLOOR HOLD-DOWN SCHEDULE					
Shear wall ID	Hold down studs	Hold down anchor type	CL (in)	Type (see key plan)	
SW_N1C	(1)	Simpson HDU4-SDS2.5	1 5/16	1	
SW_N1A	(3)	Simpson HDU11-SDS2.5	1 3/8	=	
SW_E1C	(3)	Simpson HD19	2 1/8	Ш	6.6
SW_W1C	(3)	Simpson HD19	2 1/8		0.0
SW_E1A	(4)	Simpson HD19	2 1/8	IV	
SW_EC1C	(4)	Simpson HD19	2 1/8		
SW_S1A	(4)	Simpson HD19	2 1/8		
SW_S1B	(4)	Simpson HD19	2 1/8		8.1
SW_W1A	(4)	Simpson HD19	2 1/8		
SW_WC1A	(4)	Simpson HD19	2 1/8		
SW_WC1C	(4)	Simpson HD19	2 1/8		

2.875

5.875

6.625

8.125