

MASONRY WALL REINFORCING SCHEDULE			
MARK	WALL THICKNESS	VERTICAL REINFORCEMENT & SPACING	REINFORCEMENT LOCATION IN CELL
MW.1	8"	#5 AT 48" o/c MAX	CENTER
MW.2	8"	#6 AT 16" o/c MAX	INSIDE FACE

MASONRY WALL REINFORCING SCHEDULE NOTES:
1. GROUT CONCRETE MASONRY UNITS SOLID FULL HEIGHT AT REINFORCEMENT LOCATIONS.
2. UNLESS NOTED, USE #5 14" O/C VERT. REINFORCEMENT.
3. PROVIDE 1/2" DEEP MASONRY UNIT WALL REINFORCING ABOVE AND BELOW ALL MASONRY OPENINGS: EXTEND THE LENGTH OF THE REBARS BY 23" OR 40 BAR DIAMETERS PAST THE EDGE OF THE OPENING.
4. REINFORCING TO BE HOT-DIPPED GALVANIZED.
5. PROVIDE STANDARD (W1) HORIZONTAL JOINT REINFORCING AT 10' ON CENTER VERTICALLY (8' ON CENTER IN PARAPET WALLS) UNO.
6. MASONRY FIREWALL CONSTRUCTION ASSUMES MASONRY BLOCKS COMPRISED OF LIMESTONE.

MASONRY WALL FOOTING SCHEDULE			
MARK	WIDTH	THICKNESS	LONGITUDINAL
MWF.1	2' - 0"	1' - 0"	(2) #5
MWF.2	3' - 0"	1' - 2"	(3) #5

MASONRY WALL FOOTING SCHEDULE NOTES:
1. REFER TO STRUCTURAL NOTES SHEET FOR LAPs IN STEEL REINFORCEMENT.
2. REFER TO FOUNDATION PLAN FOR TOP OF FOOTING ELEVATIONS.
3. ALL FOOTING EXCAVATIONS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE.

THICKENED SLAB SCHEDULE			
MARK	DIMENSIONS	REINFORCEMENT	REMARKS
TS20	2' - 0" x (CONT)	THICKENED SLAB, REFER TO 11/	

THICKENED SLAB SCHEDULE NOTES:
1. REFER TO STRUCTURAL NOTES SHEET FOR LAPs IN STEEL REINFORCEMENT.
2. REFER TO FOUNDATION PLAN FOR TOP OF FOOTING ELEVATIONS.
3. ALL FOOTING EXCAVATIONS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE.

WALL FOOTING SCHEDULE			
MARK	DIMENSIONS	REINFORCEMENT	
WF26	2' - 6" x (CONT)	LONGITUDINAL	
WF26	2' - 6" x (CONT)	TRANSVERSE	#5's AT 12' BOTTOM FACE

COLUMN FOOTING SCHEDULE NOTES:
1. REFER TO STRUCTURAL NOTES SHEET FOR MINIMUM COVER REQUIREMENTS.
2. REFER TO FOUNDATION PLAN FOR TOP OF FOOTING ELEVATIONS.
3. ALL FOOTING EXCAVATIONS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE.
4. ALL LAPs IN STEEL REINFORCING SHALL BE CLASS "B" LAP SPLICES UNLESS NOTED OTHERWISE.














COLUMN FOOTING SCHEDULE					
MARK	W	L	D	BOTTOM REINFORCING	COLUMNS
FT100a	9'-0"	9'-0"	1'-8"	(10)-#7	A1 A2
FT100b	9'-0"	9'-0"	1'-8"	(10)-#8	A3 A4 A5
FT100a	9'-6"	9'-6"	1'-8"	(10)-#7	B2
FT100b	9'-6"	9'-6"	1'-8"	(10)-#8	B3 B4 B5
FT110	10'-0"	10'-0"	2'-1"	(11)-#8	F1 F2 F3 F4 F5
FT110b	10'-6"	10'-6"	2'-3"	(11)-#8	C1
FT110a	11'-0"	11'-0"	2'-1"	(12)-#8	G2 G3 G4 G5
FT110b	11'-0"	11'-0"	2'-3"	(12)-#8	D1 G1
FT116	11'-6"	11'-6"	2'-1"	(12)-#8	C2 C3 C4 C5
FT120	12'-0"	12'-0"	2'-3"	(13)-#8	D2 D3 D4 D5

COLUMN FOOTING SCHEDULE NOTES:
1. REFER TO STRUCTURAL NOTES SHEET FOR LAPs IN STEEL REINFORCEMENT.
2. REFER TO FOUNDATION PLAN FOR TOP OF FOOTING ELEVATIONS.
3. ALL FOOTING EXCAVATIONS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE.

CONCRETE WALL REINFORCING SCHEDULE				
MARK	TYPE	THICKNESS	REINFORCEMENT	REMARKS
W1	CONCRETE	10"	5#'s AT 18" o.c.	Inside face
W2	CONCRETE	10"	5#'s AT 12" o.c.	5#'s AT 12" o.c. inside face
W3	CONCRETE	10"	6#'s AT 12" o.c.	inside face
W4	CONCRETE	8"	4#'s AT 12" o.c.	3#'s AT 12" o.c. centered in wall thickness


CONCRETE WALL REINFORCING SCHEDULE NOTES:
1. REFER TO STRUCTURAL NOTES SHEET FOR LAPs IN STEEL REINFORCEMENT.
2. COORDINATE AND VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS AND EXIST. CONDITIONS

Date	Description
07.08.2019	Footing/Foundation Permit
08.15.2019	75% CD Set
08.21.2019	Permit
09.25.2019	<Progress>




Date	Description
07.08.2019	Footing/Foundation Permit
08.15.2019	75% CD Set
08.21.2019	Permit

Date	Description
07.08.2019	Footing/Foundation Permit
08.21.2019	Permit
09.25.2019	<Progress>







Date	Description
08.15.2019	75% CD Set
08.21.2019	Permit
09.25.2019	<Progress>





WOOD FLOOR PLAN KEYED NOTES:

- ① 24" DEEP PARALLEL CHORD FLOOR TRUSSES AT 24" o/c.
- ② 24" DEEP PARALLEL CHORD FLOOR TRUSSES AT 12" o/c.
- ③ PREFABRICATED SIDE HUNG METAL BALCONY, BY OTHERS
- ④ 3 1/2" x 6" JOISTS AT 32" o/c.

"SEE HEADER/POST SCHEDULE IN S216 SHEET"
"SEE SHEAR WALL SCHEDULE IN S216 SHEET"





WOOD FLOOR PLAN KEYED NOTES:

- ① VARIABLE DEPTH PARALLEL CHORD ROOF TRUSSES AT 24" o/c.
- ② 2 1/2" x6" JOISTS AT 16" o/c
- ③ PREFABRICATED SIDE HUNG METAL BALCONY, BY OTHERS
- ④ 3 1/2" x6" JOISTS AT 32" o/c.

"SEE HEADER/POST SCHEDULE IN S216 SHEET"
"SEE SHEAR WALL SCHEDULE IN S216 SHEET"

CAPITAL GROUP
Developer: W Capital Group
tyler@wcapitalgroup.com | 608.345.6458

OpeningDesign
Architect: OpeningDesign
316 W Washington Ave | Suite 675
Madison, WI 53703
ryan@openingdesign.com | 773.425.6456

ROYAL CONSTRUCTION
General Contractor: ROYAL CONSTRUCTION
3453 Greenway Street | Eau Claire, WI 54701
jim@royalbuilt.com | 715-225-6377

Cedar Corporation
Civil Engineer: CEDAR CORPORATION
404 Wilson Avenue | Menomonie, WI 54751
kevin.colm@cedarcorp.com | 715-235-9081

XC
Structural Engineer: XC Structural Engineering
Calle Apolonia Morales, 628036 Madrid,
l.perezato@xcengineering.xyz | +34 610 56 26 37

Innovation
Engineering Services Incorporated
4729 Dale-Curtin Dr. McFarland, WI 53558
khsay@innovation-built.com

Hovland's Heating - Ventilation - Air Conditioning
Mechanical Engineer: HOVLAND'S HVAC
10954 E. Melby Street | Chippewa Falls, WI 54729
jansen@hovlands-inc.com | 715.552.5595

PRISM DESIGN ELECTRICAL CONSULTANTS INC.
Electrical Engineer: PRISM DESIGN ELECTRICAL CONSULTANTS INC
E8403 State Rd 85 | Mondovi, WI 54755
bhalgren@prismdesign-electrical.com | 715.797.0602

TAILORED ENGINEERING
Plumbing Engineer: TAILORED ENGINEERING
1600 Aspen Commons | Ste 210 | Middleton, WI 53562
bnovak@tailoredeng.com | 608.209.7500

Date	Description
08.15.2019	75% CD Set
08.21.2019	Permit
09.25.2019	<Progress>

6


5

4


3

2


1




6 FLOOR FRAMING AT SECOND FLOOR, EXTERIOR BEARING WALL




9 FLOOR FRAMING AT LOBBY, COURTYARD STEEL BEAM




11 FLOOR FRAMING AT LOBBY, INTERIOR BEARING WALL




7 CANTILEVER SECTION



C15x40 DETAIL



8 CANTILEVER, LATERAL VIEW




10 FLOOR FRAMING AT LOBBY, CORRIDOR STEEL BEAM

Date	Description
08.15.2019	75% CD Set
08.21.2019	Permit
09.25.2019	<Progress>

Date	Description
08.15.2019	75% CD Set
08.21.2019	Permit
09.25.2019	<Progress>

6 | 5 | 4 | 3 | 2 | 1



CAPITAL GROUP
Developer: W Capital Group
tyler@wcapitalgroupre.com | 608.345.9848

d
Architect: OpeningDesign
316 W Washington Ave | Suite 675
Madison, WI 53703
ryan@openingdesign.com | 773.425.6456

ROYAL CONSTRUCTION
General Contractor: ROYAL CONSTRUCTION
3453 Greenway Street | Eau Claire, WI 54701
jim@royalbuilt.com | 715-225-6377

Cedar
Civil Engineer: CEDAR CORPORATION
404 Wilson Avenue | Menomonie, WI 54751
kevin.colm@cedarcorp.com | 715-235-9081

XC
Structural Engineer: XC Structural Engineering
Calle Apolonia Morales, 628036 Madrid,
l.perezato@xcengineering.xyz | +34 610 56 26 37


Innovation
Engineering Services Incorporated
4729 Dale-Curtin Dr, McFarland, WI 53558
kfrey@innovation-built.com

Hovland's
Heating • Ventilation • Air Conditioning
Mechanical Engineer: HOVLAND'S HVAC
10954 E Melby Street | Chippewa Falls, WI 54729
jhansen@hovlands-inc.com | 715.552.5595


PRISM DESIGN
ELECTRICAL CONSULTANTS INC.
Electrical Engineer: PRISM DESIGN ELECTRICAL CONSULTANTS INC
EB403 State Rd 85 | Mondovi, WI 54755
bhalgren@prismdesign-electrical.com | 715.797.0602

TAILORED ENGINEERING
Plumbing Engineer: TAILORED ENGINEERING
1600 Aspen Commons | Ste 210 | Middleton, WI 53562
bnovak@tailoredeng.com | 608.209.7500


4 ELEVATION - NORTH FOUNDATION WALL



1 ELEVATION - EAST FOUNDATION WALL



2 ELEVATION - SOUTH FOUNDATION WALL



3 ELEVATION - WEST FOUNDATION WALL

ELEVATIONS - FOUNDATION
CANNERY TRAIL RESIDENCES - 1750 N OXFORD AVE. - EAU CLAIRE, WI

S300
10/1/2019 11:47:04 AM

Date
09.25.2019
Description
<Progress>

Date	Description
09.25.2019	<Progress>

Date	Description
09.25.2019	<Progress>

CANNERY TRAIL RESIDENCES - 1750 N OXFORD AVE. - EAU CLAIRE, WI

ENLARGED PLANS S400

